AMERICAN RIVER WATERSHED COMMON FEATURES, WATER RESOURCES DEVELOPMENT ACT OF 2016, SACRAMENTO RIVER EAST LEVEE (SREL) CONTRACT 4

Draft Supplemental Environmental Assessment/ Environmental Impact Report

Sacramento District US Army Corps of Engineers









If you have joined by computer and computer audio, you will only see the panelist and the presentation deck.

For audio problems help, use the Q&A chat at the bottom of the screen

Computer Use	Phone Only Use
- You will be muted upon entry	- To raise your hand, use *9
- To "raise hand", click on three dots	- We will un-mute you.
- Please lower hand after comment	
- We will un-mute you during Q&A	
- To write comments, click on the Q&A icon at the bottom of the screen	





Draft Supplemental EA/EIR is available at: sacleveeupgrades.com

Public Comment Period: June 15 – August 1, 2022

CEQA Certification: Expected October 2022

Final Document: Expected November 2022





American River Watershed Common Features 2016 Project
 Final Environmental Impact Statement / Final Environmental Impact Report

Sacramento River East Levee Contract 4

 Supplemental Environmental Impact Report/ Environmental Assessment (SEA/SEIR)


Opportunities for Public Input



AMERICAN RIVER COMMON FEATURES (ARCF) 2016



- Water Resources Development Act of 2016
- Emergency Supplemental Appropriations in the Bipartisan Budget Act of 2018












AMERICAN RIVER COMMON FEATURES (ARCF) 2016






SUPPLEMENTAL TARGET JAN 2024

Authorized Plan

Features	
North Area Streams Seepage	4 miles
Sacramento River Seepage	9 miles
American River Erosion	11 miles
Sacramento River Erosion	10 miles
Levee Stabilization	5 miles
Levee raises	5 miles
Widen Sacramento Weir and Bypass	1500 feet
Reduces Risk	500,000 people
	125,000 structures
	\$62 billion protection




CAUSES OF LEVEE FAILURE







CAUSES OF LEVEE FAILURE










CAUSES OF LEVEE FAILURE














Atchison County, MO - 2011




2017 Flood - Riverview Court, Little Pocket.




SEEPAGE & STABILITY ISSUES ADDRESSED







SREL CONTRACT 4 OVERVIEW





- 2.3 Miles of Seepage Cutoff Wall
- 0.12 Miles of Berm
- 0.37 Miles of Levee Raise

SREL Contract 4 Remediation Summary							
GRR Reach ID	SREL Reach ID		diation oning End	Remediation Length (ft)	Remediation Type		
D	Α	1027+50	1039+00	1150	Levee Raise w/ Shallow Cutoff Wall		
Е	10 - 11-2	1244+70	1250+00	530	Jet Grout Cutoff Wall		
E	11-3	1250+00	1261+75	1175	SB Cutoff Wall		
F	23	1530+30	1534+00	370	Jet Grout Cutoff Wall		
	N	1676+00	1678+00	200	Levee Raise		
		1678+00	1710+29	3229	Shallow Cutoff Wall		
		1689+00	1690+00	100	Seepage and Stability Berm		
G	0	1710+29	1719+60	931			
		1725+50	1728+75	325	Shallow Cutoff Wall		
	Р	1730+50	1766+00	3550			
		1766+00	1772+00	600	Levee Raise		
N	NDU		1774+00	380	Jet Grout Cutoff Wall		
	NBLL	1773+00	1778+20	520	Seepage and Stability Berm		



SREL CONTRACT 4 OVERVIEW











SREL CONTRACT 4 OVERVIEW














U.S.ARMY

TYPICAL CUTOFF WALL CROSS SECTION



CONTRACT 4 CONVENTIONAL (OPEN TRENCH) CUTOFF WALL



Notes:


- (1) Levee height shown at 20 feet. Dimensions will vary based on actual levee height.
- 2 Levee to be degraded by a minimum of 3 feet, up to 1/2 levee height, for cutoff wall construction and then rebuilt with low permeability levee embankment fill (Type 1).
- (3) Existing vegetation on the waterside and landside would not be disturbed unless designated to be removed.
- Crown resurfacing not shown.

Source: GEI & HDR 2014, adapted by GEI 2019






WORK AREAS NORTH OF MILLER PARK – JET GROUT CUTOFF WALLS







Source: Science Direct https://doi.org/10.1016/j.jrmms.2008.10.005



3/11/2021 HPC




SREL C4 – ACCESS, STAGING, AND HAUL ROUTES



MA	MARCH – DECEMBER 2023				
Cutoff Wall	10,580 feet				
Staging Areas	 Interior Drainage Sump 132 Garcia Bend Park Bill Conlin Sports Complex (Empty field) 1 Waterside Staging Areas Railyards (empty field) Front St Broadway Westin Hotel Valet Parking Lot Landside Near Cosumnes River Blvd North Beach Lake Levee Empty 				
Access Points	 Jibboom Street Railyards Blvd Front Street Broadway Sutterville Road Riverside Blvd Pocket Rd Interior Drainage Sump 132 Garcia-Bend Park Freeport Blvd 				



GARCIA-BEND PARK STAGING AREA






- Owner: City of Sacramento
- Approx. 1.4 acres
- Within Garcia-Bend Park boat launch parking lot
- Restoration of the boat launch Parking Lot following completion of the jet grout cutoff wall at the Pocket Canal levee segment.
- Construction of the jet grout cutoff wall and parking lot restoration may require temporary closures of the boat launch at its parking lot.















21
















SUPPLEMENTAL EA/EIR TOPIC AREAS ANALYZED




- Visual Resources
- Hydrology and Water Quality
- Vegetation and Wildlife
- Fisheries
- Special Status Species
- Cultural Resources
- Transportation and Circulation
- Geological Resources

- Air Quality
- Greenhouse Gas Emissions and Energy Consumption
- Noise
- Recreation
- Public Utilities and Service Systems
- Hazardous Materials
- Socioeconomic, Population, and Environmental Justice



IMPACTS







MITIGATION MEASURES





Detour Routes



Dust Control



Vibration Monitoring



Water & Air Quality Monitoring



VEGETATION & WILDLIFE





Trimming and Removing Trees Outside of Bird Nesting Season and to Protect Bats



No impact to fisheries



Creation of new habitat



Comprehensive Monitoring by Qualified Biologists



HABITAT MITIGATION SITE



Beach Stone Lakes Mitigation Site (24.2 acres) - Diverse oak woodland habitat near Cliff's Marina





ANTICIPATED CONSTRUCTION SCHEDULE



Pre-construction (November 2022 (March 2023) – Site prep, cut and trim trees

Construction Contract Award (January 2023)

- Submittals, site reconnaissance, preparation and mobilization

Site Construction (March 2023 - Fall/Winter 2023)

- Construct seepage/stability levee improvements



FOR MORE INFORMATION...





About * Business With Us * Missions * Locations * Careers * Media * Library Contact * Coronavirus

acramento **Q**

* / Missions / Civil Works / Sacramento Levee Upgrades / Sac River Levees



Project Overview

2022 will see two miles of levee improvements in Big Pocket

American River Levees

Sacramento River Levees

The Sacramento Metropolitan area is one of the most at risk areas for flooding in the United States due to its location at the confluence and within the floodplain of two major rivers. The 1997 Sacramento flood events revealed deep under-seepage on the Sacramento River, including in areas that were remediated to address through-seepage with shallow cutoff walls in the early 1990s.

Construction is set to begin this spring on two miles of levee improvements in the Pocket neighborhood. The work will entail installation of a seepage cutoff wall from Surfside Way at the northern end of down to Sump 132 at the Pocket Canal on the southern end.

Sacramento Weir

Mitigation

This is the third major construction contract to address seepage and stability concerns with the levee between Old Sacramento and the Freeport Regional Water Intake Facility near Sacramento's Pocket neighborhood. In 2020, construction crews installed nearly three miles of seepage cutoff wall along the Sacramento River East Levee, and a 400-foot-long seepage berm on the landside levee adjacent to Front St. In 2021, USACE contractors installed approximately 1.8 miles of seepage cutoff wall at four locations, including on both sides of Business 80/Highway 50 just upstream of Miller Park, on the south side of the little pocket, and on the north side of the big pocket. In total, the American River Common Features 2016 project is expected to construct approximately 9 miles of slurry cutoff walls along the Sacramento River East Levee, and will add erosion protection at a number of locations.



merican River Com...

Current Project Activities

Sacramento River Erosion Contract 1

Sacramento River Erosion Contract 2

Sacramento River East Levee Contract 2 Construction

Sacramento River East Levee Contract 3 Construction

sacleveeupgrades.com



NEPA/CEQA COMMENTS



Draft Supplemental EA/EIR is available at:

sacleveeupgrades.com

Public Comment Period: June 15 – August 1, 2022

CEQA Certification: Expected October 2022

Final Document: Expected November 2022



HOW TO PROVIDE COMMENTS



1. Write:

Kalia Schuster Department of Water Resources 3310 El Camino Ave, Annex Suite 200 OR Sacramento, CA 95821

Public Affairs Office U.S. Army Corps of Engineers 1325 J Street Room 1513 Sacramento, CA 95814

2. Email: PublicCommentARCF16@water.ca.gov

ARCF_SRELC4@usace.army.mil

Please include "SREL Contract 4 SEA/SEIR" in subject line



CLARIFYING QUESTIONS





Please "raise hand" and limit question to 3 minutes Computer: click on three dots Phone: enter *9