AMERICAN RIVER COMMON FEATURES 2016

Sacramento River East Levee, Contract 2 Industry Day



May 6, 2020












PROGRAM OVERVIEW		
Project Background		
TECHNICAL OVERVIEW		
Overview		
Remaining Efforts		
Environmental		
REGIONAL OVERVIEW		
CONTRACTING		



SACRAMENTO AREA PROJECTS








AMERICAN RIVER COMMON FEATURES 2016





SUBSTANTIAL COMPLETION TARGET JAN 2024

Authorized Plan			
Features			
Cutoff walls	Up to 13 miles		
Bank protection	Up to 21 miles		
Levee stabilization	Up to 5 miles		
Levee raises	Up to 5 miles		
Widen Sacramento Weir and Bypass	Approx. 1500 feet		
Environmental Mitigation	Up to 680 acres		
Replant Shaded Riverine Habitat	Up to 15.5 miles		
Reduces Risk	500,000 People		
	125,000 Structures		
	\$62 Billion		



SACRAMENTO RIVER EAST LEVEE (SREL) CONTRACT 2 IMPROVEMENTS

"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."








SREL CONTRACT 2 - SCHEDULE







SREL CONTRACT 2 REMAINING EFFORTS



SACRAMENTO RIVER EAST LEVEE SEEPAGE/STABILITY/OVERTOPPING

SREL Contract 2 – 90% and 100%

ENGINEERING REVIEWS

Value Engineering Study


PROCUREMENT PROCESS

20MAY20 – 23JUN20– 90% Draft Solicitation

6MAY20 – Industry Day

FY21 QTR 1 - Solicitation

FY21 QTR 2 - Award



CONSTRUCTION


NLT 30 SEPT 2021 – Cutoff Wall and Levee Reconstruction Complete


NLT DEC 2021 – Construction Complete



SREL CONTRACT 2 OVERVIEW










SREL CONTRACT 2 OVERVIEW







REACH 4 JET GROUT CUTOFF WALL



Cutoff Wall





REACH 4 JET GROUT CUTOFF WALL



1097

120" RCP SD OUTFALL PROTECT IN PLACE

EXISTING SHEET PILE PROTECT IN PLACE

PROTECT IN PLACE

REMOVE AND REPLACE


2" RCP WATER PIPE PROTECT IN PLACE

EXISTING SHEET PILE

PROTECT IN PLACE

120" and 42" Pipe Utility Vault

- Wall Alignment Jogs to Waterside limit of Vault
- Panel Construction Required for Crossing Pipes





Google Earth

9 2020 Google

REACH 5 & 6: JET GROUT CUTOFF WALL







Cutoff Wall


- 50 FT Depth
- 1,300 FT Length
- No Levee Degrade

Levee Crest Railroad

One Set of Tracks – Limited Use for Public Tours. Will run on weekends only.

Utility Conflicts

Various –
 Petroleum/Gas/Com/
 Water/ Overhead
 Electrical






REACH 5 & 6: JET GROUT CUTOFF WALL



Various Utility penetrations through out levee within Cutoff Wall Extents


- All are 24" or less in diameter
 - 17 to be Abandoned in Place
 - 14 to be Protected in Place





REACH 4, 5, & 6 STAGING AREAS







Google Earth

REACH 13 SB CUTOFF WALL








Cutoff Wall

- 63 FT Depth
- 920 FT Length
- ~5 FT of Levee Degrade <u>Utility Conflicts</u>
- 1 Piezometer Removal and Disposal
- 1 Pipe Removal and Disposal






REACH 13 SB CUTOFF WALL



- Tie-in into SREL Contract 1 DMM Wall at U/S end
- 2 Protect in Place penetrations D/S of Wall end



U.S.ARMY

REACH 13 STAGING AREA







REACH 15, 16, & 17 CUTOFF WALL




Cutoff Wall

- Combined 1.3 Miles of SB(Yellow) / SCCB(Green) / DMM(Blue) Cutoff Wall
- Degrade
- Wall depths: 72 118 ft

Utility Conflicts

- 12 Removal and Disposals Small diameter (≤12" Waterlines/Electrical Conduits/Misc)
- Sump 63 Vault and Discharge Pipes (4) Removal and Replacement







PHASE II CUTOFF WALL TRENCH STABILITY



- Cracking of levee and foundation and loss of slurry occurred at five locations during construction of USACE Phase II SCB walls in 1992.
- Trench failures occurred while the trenches were supported by bentonite slurry, and prior to or during placement of final backfill material.
- All five sites are located within extents where SRELIP cutoff wall is proposed.
- Levee and foundation were excavated to about El. 7.5-13.5, followed by placement of geotextile
 and geogrid layers, reconstruction of levee, and reconstruction of cutoff wall.








REACHES 15-17 SUMP 63







SUMP 132 STAGING AREA





Owner: City of Sacramento
Approx. 1.3 acres
Within Sump 132 facility


Special considerations

- Operational facility and access must be maintained for City personnel.
- Existing utilities throughout facility



GARCIA-BEND PARK STAGING AREA





- Owner: City of Sacramento
- Approx. 1.4 acres
- Within Garcia-Bend Park boat launch parking lot
- Special Considerations:
 - Existing utilities throughout facility



SREL C2 - HAUL ROUTES





Limit impact to residential communities by traveling on highways, major streets, and levee crown to extent practical.

Highways and major streets include:

- Interstate 5
- Front Street
- Broadway
- Riverside Drive
- Seamas Avenue
- 43rd Avenue
- Riverside Boulevard
- Florin Road
- Pocket Road



SREL C2 – LEVEE ACCESS POINTS





- Access is limited due to residential areas
- 14 designated access points to levee crown



POTENTIAL BORROW AND DEGRADE MATERIALS



Borrow Material (Type 1 Fill)

- Potential Source: Sacramento Regional Wastewater Treatment
 Plant
 - Echo Water Project Spoil Stockpiles

Reuse of Excavated Materials

- Levee crown degrade is typically a sandier fill that does not meet levee fill (Type 1) requirements
- Unused degrade material can potentially be transported to the Railyards project





APPROXIMATE QUANTITIES



Levee Degrade (CY)	Levee Fill (Type 1) (CY)	SB Cutoff Wall (SF)	SCCB Cutoff Wall (SF)	DMM Cutoff Wall (SF)
85,000	85,000	420,000	70,000	140,000

- Levee Fill Type 1 is for levee reconstruction
- All NEPA/CEQA/Section 106 documentation is required contractor proposed borrow/disposal
 - USACE Environmental Documentation –Covered in Spec
 - Commercial Source with Mining Permit

NEEDED: MEET OR EXCEED EXPECTATIONS ON ALL ACCOUNTS



SS&O ENVIRONMENTAL

CONSTRAINTS

Impacts to Elderberries: Elderberries in Project Footprint to protect in place

Impacts to Migratory Birds and Raptors

Impacts to Air/Noise Pollution

Impacts to Recreation (Bike/Pedestrian Paths, Boat Launches, Etc.)

WORKING HOURS & WINDOWS				
WORK	HOURS	FLOOD SEASON	CLEARING AND TREE TRIMMING	IN-WATER-WORK
_	v – Friday – 7pm			
Saturday	7am – 6pm	15 April – 31 October	1 November – 15 February	1 August – 31 October
Sunday 8	Зат – брт			











- Tree Removal will be completed via separate contract starting in Fall 2020.
 - SREL Contract 2 will be responsible for tree stump removal.
- Tree Trimming may be necessary
- Elderberries will be transplanted via separate contract starting Fall 2020





REGIONAL OVERVIEW



"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."



U.S.ARMY


SYSTEMATIC OVERVIEW



Project	Anticipated Construction Schedule	Description	
NATOMAS			
Reach I Contract 1	2019-2020	~ 4 miles Levee Improvements - Cut-Off Wall	
Reach H	2019-2020	~ 4 miles Levee Improvements - Cut-Off Wall	
Reach B	2020-2021	~ 2 miles Levee Improvements - Seepage berm, Relocation of Riverside Canal	
Reach E	2021-2022	~ 3 miles Levee Improvements – possible cut-off wall	
Reach A	2022-2023	~ 4 miles Levee Improvements – possible cut-off wall & numerous Utility Relocations	
Reach F&G	2023-2024	~ 4 miles Levee Improvements – possible cut-off wall	
FOLSOM DAM RAISE			
Dike Raise	2019-2024	~ 5 miles of 3.5' Dike Raise and related work in various packages	
Main Dam	2022-2025	Retrofit of up to 8 gates on the Main Dam	
HAMILTON CITY	2019-2020	Mitigation and Planting	
TULE RIVER	2020-2024	10' Spillway Raise, utility relocations, environmental mitigation	
ARCF 2016			
Sac River Levees	2019-2024	Up to 9 miles of cut-off wall and other seepage control features	
Sac River Erosion	2021-2024	Up to 10 miles of bank protection work	
Amr River Erosion	2021-2024	Up to 11 miles of bank protection work	
Sac Weir/Bypass	2022-2024	1,500 If expansion of existing gated weir at Sac Bypass	
Mitigation	2019-2024	Tree cutting, planting, maintenance, etc.	
ISABELLA			
Dams & Spillways	Ongoing	Construction of 16' dam raise, new emergency spillway, and various improvements	
Site Restoration	2020-2022	Construction of permanent operations building, site restoration and misc. construction	
YUBA RIVER BASIN			
Phase 2C	2019-2020	~ 1,000 If DSM wall construction	
Phase 2B/3	2020-2023	~ 13,000 LF Cut-off wall construction	
Phase 4B	2022-2023	Rock Slope Protection installation	
PL 84-99	2018-2020	Various repairs in response to 2017 Flood Event	
SUTTER BASIN	2019-2020	~ 5 miles of Levee Improvements including cut-off wall	
LOWER SAN JOAQUIN	Unknown	Project is entering design phase and may have a contract as early as 2021	
WEST SACRAMENTO	Unknown	Project is seeking to enter design phase and may have a contract as early as 2022	

U.S.ARMY

SYSTEMATIC OVERVIEW – CALTRANS PROJECT



I-5 Corridor Enhancement Project/I-5 HOV Lanes

On Interstate 5 (I-5) from 1.1 mile south of Elk Grove Boulevard Over crossing (PM 9.7) to American River Viaduct (PM 24.9) will rehabilitate pavement and other related assets, construct new High Occupancy Vehicle (HOV) lanes, install new fiber optic lines and extend the I-5 northbound #1 lane to improve the on ramp merge and weave movement

Total Project Cost: \$370 million

Construction: Summer 2019 – Fall 2022



CONTRACTING



"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."





HOW TO OBTAIN SOLICITATIONS



HOW TO OBTAIN SOLICITAITONS		
SAMbeta - Beta.sam.gov		
Search by Solicitation Number		
View Interested Vendors List and register as an interested vendor		
Requirements to download Technical Data Package:Beta.sam.gov		
Register to receive notifications and updates/amendments		
Technical information will be posted on the BetaSam website		

SMALL BUSINESS GOALS CATEGORY	GOAL
Small Business (SB)	25%
Small Disadvantaged Business (SDB)	20%
Woman Owned Small Business (WOSB)	4%
Service Disabled Veteran Owned Small Business (SDVOSB)	3%
Historically Underutilized Business Zone (HUBZone)	3%

CONTRACT ADMINISTRATION

USACE Safety Manual, EM 385-1-1

Quality Assurance Surveillance Plan for Services

USACE Resident Management System (RMS) & Quality Control System (QCS) will be used for construction

Government is committed to partnering process at all levels



INDUSTRY FEEDBACK



PROJECT CHALLENGES

Production/Productivity Rates (Efficiency/Effectiveness, Constraints, Innovations)

Material/Equipment Availability - Number of rigs operating in the US

Air Quality (Availability of higher tiered equipment/barges, recent model year equipment, innovations)

Contract Process Innovations/Improvements

REQUESTED AREAS OF FOCUS

Specified requirements for column diameter; air, water and grout injection pressures and flow rates; grout water/cement ratio.

Requirements for settlement and heave monitoring and control for existing railroad track and pipelines that are adjacent or cross the work.

Quality control requirements.

Ability to install jet grout columns and panel to depths of at least 115 feet

Typical production rates at depths of 115 feet

Working hours; preferences for working multiple shifts versus multiple rigs working one shift

WHAT'S NEXT

Draft Plans and Specifications

 $\underline{\text{https://beta.sam.gov/opp/dfd2aaa1a57f423aba47d8b33304b0b1/view?keywords=\%22Sacramento\%20River\%20East\%20Levee\%22\&sort=\underline{\text{relevance\&index=\&is_active=true\&page=1}}$

Contract Specific Industry Days



QUESTIONS/COMMENTS/CONCERNS...







Project Overview

American River Levees

Sacramento River Levees

Sacramento Weir

Subscribe for Construction & Traffic email updates



Sacramento River News

Levee improvements at six locations on tap for 2020

The Sacramento Metropolitan area is one of the most at risk areas for flooding in the United States due to its location at the confluence and within the floodplain of two major rivers. The 1997 Sacramento flood events revealed deep underseepage on the Sacramento River, including in areas that were remediated to address through-seepage with shallow cutoff walls in the early 1990s.

We are currently underway with construction on Sacramento River East Levee Contract 1, which includes construction of approximately 3 miles of levee improvements--to include a combination of seepage cutoff walls and seepage berms--at 5 locations along the Sacramento River East Levee. Site preparation was completed in January 2020, and levee construction is scheduled to continue through December 2020.

A 400-foot-long seepage berm was constructed earlier this year on the landside levee adjacent to Front St, wrapping up in January 2020. In total, the American River Common Features 2016 project is expected to construct approximately 9 miles of slurry cutoff walls along the Sacramento River East Levee, and will add erosion protection at a number of locations.

Current Project Activities